



Vestil Manufacturing Company

2999 North Wayne Street, P.O. Box 570, Angola Indiana 46703

Telephone (260) 665-7586 * Fax (260) 665-1339

Certificate of Compliance and Capacity Verification

Vestil certifies that this MULTI STATION JIB CRANE TRANS 1K 85X112 model number JIB-P-10-8-6, complies with all applicable U.S. Federal OSHA regulations and U.S. national standards which are incorporated into U.S. national laws and/or regulations.

Capacity verification: A test weight in the range of 100% to 125% of the maximum rated load is applied to randomly selected sample units. Afterwards, the sample unit was visually inspected. Inspection confirmed the soundness of all welds, i.e. no permanent deformations or other forms of damage.

The end user bears the responsibility to ensure safe, normal operability by testing and inspecting the unit periodically and in accordance with instructions provided with the unit.

Date of Issuance: 08/15/2023